



Long Island Pier | Boston Harbor Islands

BOSTON, MASSACHUSETTS

Completing a process begun in 2002 to expand public access to Long Island, Cashman was responsible for the construction of a permanent pier on this Boston Harbor island.

PROJECT HIGHLIGHTS

- Both concept and initial design were performed by Jay Cashman, Inc.
- The 455 foot-long pier was constructed from Inverset slabs recycled from Boston's Big Dig.
- Entire pier clad with IPE wood.
- Cashman drove fifty-four 18-inch piles and installed all structural steel headers and bracing.
- Assembled decking members, applied IPE cladding and attached utilities to pier sections in yard while piles were being driven.
- Entire job completed on schedule in three months.

Location:	Boston Harbor Islands Boston Harbor
Contractor:	Jay Cashman, Inc.
Contract Dates:	Jan. 2008 – June 2008
Dollar Value:	\$3.7 Million
Awarding Authority / Owner:	The City of Boston

